



INSTALLATION TO BE LD3 SYSTEM WITH IN THE NEW LANDING AREA AND GROUND FLOOR HALLWAY INCLUDING ADDITIONAL HEAT DETECTORS IN THE KITCHEN. (MAKE AND MODEL TO BE DETERMINED) WILL HAVE MAINS ELECTRICAL SUPPLY AND WILL BE INTERLINKED. THE ALARM SOUND TO BE A MINIMUM OF 75DB AT THE BED-HEAD FURTHEST AWAY FROM THE ALARM.

